BRUHAT BANGALORE MAHANAGARA PALIKE

MODIFIED APPROVED SCHEDULE - B

Name of the work: Modified Estimate For Improvements of roads and drains in Amruthahalli S.C. Colony in 1st and 3rd Cross ward no. 07 Byatarayanapura, Kodigehalli sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Quotation Rates of A. Manjunath	
				In Figures	In Words
1	501.20	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	102.11	Rupees One Hundred Two and Eleven Paise Only
2	102.19	KSRB 4-1.3 : Providing and laying in position **plain cement concrete of mix 1:4:8** with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, **in foundation**, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	4676.42	Rupees Four Thousand Six Hundred Seventy Six and Forty Two Paise Only
3	153.29	Providing and laying **cement concrete** using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - **Ready mixed Cement concrete for Beams, Staircase and Roof with M-20**	Cum	5641.30	Rupees Five Thousand Six Hundred Forty One and Thirty Paise Only
4	3.29	KSRB 4.9.2 : Providing **T.M.T steel reinforcement for R.C.C work** including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **- TMT bars Fe 500**	Tonne	75593.86	Rupees Seventy Five Thousand Five Hundred Ninety Three and Eighty Six Paise Only
5	501.20	Lead for Disposal of debris shall be payable at Carriage rates by mechanical means including loading and unloading from 0.00 to 5.00 Km	cum	78.15	Rupees Seventy Eight and Fifteen Paise Only
6	1021.92	KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications.	Sqm	927.58	Rupees Nine Hundred Twenty Seven and Fifty Eight Paise Only

E.E. (BTP DIV)

June 2014

Sl. No.	Approved Qty.	Description	Unit	Approved Quotation Rates of A. Manjunath	
				In Figures	In Words
7	1021.92	KSRB15-3.3 : Providing 12mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.	Sqm	153.40	Rupees One Hundred Fifty Three and Forty Paise Only
8	255.48	KSRB 4-6.4 : Providing and removing **centering, shuttering, strutting, propping** etc., and removal of form work for **vertical surface** such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2	Sqm	299.65	Rupees Two Hundred Ninety Nine and Sixty Five Paise Only

Signature of the Contractor

20/04

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

20/04